

सैप्टिक टैंक हुआ पुराना - बायोफरनेस का है जमाना

Provisional Quotation

www.TozaIndia.com | info@TozaIndia.com

227 – Neelkanth Arcade, Opp St Joseph Academy

43 – Rajpur Road, Dehradun. (M) 9758828989

Quotation No. : - SEWER / 2018 / RST - /

Date: -

Name / Address: -----

(M) ----- Email: -----

Capacity of Septic Tank (As per client): ----- Uses | Quoted Value: -----

Septic Tank Uses	20	30	50	70	100	200	300	400	500
Rates in D Dun	39900	59900	99900	119900	179900	299900	459900	619900	769900
Rates other City	49900	79900	129900	149900	219900	359900	559900	749900	929900

Soak Pit / other work Details: ----- | Quoted Value: -----

	Brick Made			Readymade	Other work
Soak Pit Details	4X14F	6X14F	8X14F	2X12F	
Cost in D Dun	49900	59900	89900	59900	
Cost other city	59900	79900	99900	79900	

Payment Terms: 100% advance. GST shall be extra @ 18%. Payment: -----

Our Scope of Work (Septic Tank): - Applicable / Not applicable

Excavation, Supply and Installation of Pre-casted RCC **TrioClean BioFurnaX™** Readymade Septic Tank's chambers in parts with 4" diameter, 6" long inlet / outlet connection and round shape RCC covers are in our scope of work. Any other work like Plumbing, Flooring, extra soil removal, main hole chambers, required material for construction like cement, sand are excluded. Water filling inside tank for hydro testing shall be arranged by customer. These rates are for normal type of soil; in case of high water table water sucking arrangement with tanker shall be arranged by client. In case of rocky soil rates shall be quoted extra. Before signing agreement; it has been made clear to customer/client that AutoClean warrantee is valid if other houses hold waste water like bathroom etc passed through filtration tank and outlet connection of this tank is connected to running drain. If drain is absent or local authorities don't permit then multi soak well system shall be constructed and used alternatively and separate drainage system shall be developed for other household like bathroom/kitchen water. The inlet/center/outlet path of septic tank should be kept clear always by customer/user to achieve its full effectiveness.

Our Scope of Work (Soak Pit): - Applicable / Not applicable

Excavation and construction of round shape Readymade / honey comb tapered masonry soak pit having depth and diameter as per agreement with 4" diameter, 6" long inlet / outlet connection and RCC covers are in our scope of work. Material for construction of above said Soak pits are included. We recommend multi soak wells for efficient soaking purpose and use them alternatively. Any other work like Plumbing, Flooring, extra soil removal, sanitary manhole chambers is excluded. These rates are for normal type of soil; in case of high water table water sucking arrangement with tanker and operator shall be arranged by client. In case of rocky soil rates shall be quoted extra.

Authorized Representative

Name –

Mobile –

Signature of Recipient

Name –

Mobile -